

Caswell Park Shelter – Addendum #001

Answers in Red

1. Detail 6/A1 calls out ½" PVC liner on the bathroom ceiling, but the room finish schedule calls out gypsum. What finish should be figured? **PVC Liner panel**
2. What is the soffit material? Aluminum, Metal or prefinished Hardie soffit? **Metal**
3. What is the finish fascia material? Miratec or prefinish metal? (detail 6/A1 & 4/A1). **Painted Miratec, see detail 4/A1.**
4. Is there a flat ceiling that aligns with the 2'-8" block wing walls in front of the bathroom and mechanical room doors? What soffit material would that be then? It would appear that some type of soffit should be there since the electrical drawings are showing 6" recessed can lighting out in front of the bathroom and mechanical doors. **Yes, flat soffit with either T&G or metal liner pending on alternate approval.**
5. How is the ½" PVC liner and 2" Thermax attached to the bathroom walls? Are furring strips needed on those walls? **Z Furring**
6. Do you have specs on the ½" PVC liner material that you're thinking of? My suppliers want to make sure they are bidding the correct material. **Contractor to choose the most cost effective material.**
7. **Concrete finish on sidewalk and in the shelter seating area is to be a light broom finish with cure and seal.**
8. **Concrete finish in rooms 100, 101 and 102 are to be light broom with no cure and seal. The city will epoxy these floors at a later date.**